

Leighton Linlade Croquet Club

Date : 1 November 2022
 Our Ref : TFL/Q9208



RE : Leighton Linlade Croquet Club

To supplying all necessary labour and specialist machinery, to carrying out the following works.

Prelims				£1,420.00
Mobilisation				£2,100.00
To spray the entire existing grass area with a non-residual systemic herbicide formula (glyphosate, or similar).	3,009 m ²	@	£0.11	£330.99
By means of a Koro field top maker, remove the existing biomass (dying sward) and dispose of the green waste material to a sustainable licensed facility.	3,009 m ²	@	£0.62	£1,865.58
Allowing for 9 No loads.				£4,626.40
Further passes of the Koro field top maker, removing the upper profile of rootzone and a further quantity of the existing biomass.				
This material, more mineral than organic, will be retained on site to assist with the marrying into the existing surrounds	3,009 m ²	@	£0.21	£631.89
Cultivate the existing rootzone material (Blec buryvator - new courts area) to create a uniform tilth within the upper 150mm of rootzone. The machine will be adjusted to ensure that there is no contact with the drainage raft substrate material, ensuring this functional subsurface drainage infrastructure is left entirely undisturbed.	3,009 m ²	@	£0.62	£1,865.58
Address the cultivated area with a tractor drawn gate grader to uniformly regulate the immediate surface levels and introduce some consolidation to the upper cultivated rootzone profile.	2,500 m ²	@	£0.26	£650.00
By means of a laser-controlled box grader, grade the entire prepared (new courts) surface area to precise tolerances (+ -10 mm over a 3 m straight edge) the laser grading will remove any 'humps' trans-locating this material to areas of deficit 'hollows' ensuring surface evenness and uniformity.				
The ultimate aim is to produce a prepared surface that is both flat and level.	2,500 m ²	@	£1.08	£2,700.00

Lightly roll the prepared area with a single gang Cambridge roller, lightly consolidating the upper surface and providing a visual indicator of surface uniformity and consistency.

3,009 m² @ £0.14 £421.26

Import and spread approximately 15 mm depth of medium fine silica-based sports sand over the entire prepared court surface and lightly 'tickle' the sand into the upper rootzone profile to form a 'key' between the materials and some incorporation of the sand into the rootzone.

3,009 m² @ £2.32 £6,980.88

Supply and spread a prilled compound fertiliser (NPK designation designed to accommodate deficits identified by a detailed soils analysis). (35g/m²)

3,009 m² @ £0.11 £330.99

Supply and sow by means of a 'Brillion-type' dimpled seed box turf-maker seeding unit introduce the specified cultivars into the prepared surface at the designated seeding rate (>30 g/m²). (35g/m²)

3,009 m² @ £0.67 £2,016.03

Initiate the early grow-in phase of activities with a flat roll over the newly seeded surface area prior to the first cut, once the sward has achieved a blade height of >75 mm.

LGP rotary mower only.

£412.00

£26,351.60

Please Note -

- Above works activities subject to approval and confirmation, all areas assumed and final works will be subject to remeasure. Also assumed client adopts responsibility for any irrigation infrastructure activities required.
- We assume topsoil is already placed on site.
- No allowance has been made for watering.
- No allowance has been made for maintenance.
- Works are subject to suitable ground conditions.
- Quotation is valid for 30 days.

If you are an end user then VAT will be charged at the appropriate rate.

All prices as per Talbot Farm Landscapes Ltd terms and conditions enclosed

E. & O.E.

Talbot Farm Landscapes Ltd, Registered Office
 Talbot Farm Nursery, Derby Road, Hilton,
 Derby DE65 5FP, United Kingdom

Registered in England and Wales No: 3499467

